


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Sec. 28 Twp. 24 Rge. 13 W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/NW/NE

Lease Owner Woodman-Iannitti Oil Company  
Lease Name CURTIS Well No. 1  
Office Address Box 308, Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Date Well completed 19  
Application for plugging filed December 14 1976  
Application for plugging approved 19  
Plugging commenced December 16 1976  
Plugging completed December 22 1976  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4150'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	249'	none
				5 1/2"	4150'	3,356.68'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand to 4100' and 5 sacks cement. Shot pipe @ 3500' and 3420'.  
Pulled a total of 85 joints of 5 1/2" casing.  
Sun Cementing plugged well with 2 sacks hulls, 10 sacks gel and 100 sacks 50/50 Pozmis with 2% added gel.

12-27-76

RECEIVED  
STATE CORPORATION COMMISSION


DEC 27 1976

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.  
Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.

James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold  
Box 698, Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 23rd day of December 1976

My commission expires May 21, 1980

Marla K. Haslam Notary Public

K. T. WOODMAN  
RES. PHONE 733-0418  
OFF. PHONE 265-7650  
WICHITA, KANSAS

15-185-20636-0000  
DEC 14 1976

D. J. IANNITTI  
PHONE 792-2921  
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY  
Rotary Drilling Contractors

1008 UNION NATIONAL BUILDING  
WICHITA, KANSAS 67202

April 9, 1976

Company; Woodman & Iannitti Drilling Co.  
Farm; #1 Curtis  
Location; SE NW NE  
Section; 28-24-13W  
County; Stafford  
Contractor; Woodman & Iannitti Drilling Co.  
Comm; March 27, 1976  
Compl; April 6, 1976  
Casing; 8 5/8 @ 249 with 225 sx  
5 1/2 @ 4150 with 100 sx Elevation 1934 K.B.

Figures Indicate Bottom Of Formations

40	Clay & Sand
160	Sand
249	Red Bed
315	Red Bed
470	Red Bed
510	Sand
773	Red Bed
790	Anhy
1365	Shale & Red Bed
1700	Shale
2020	Lime & Shale
2570	Lime & Shale
2730	Lime
3025	Lime & Shale
3390	Lime
3465	Lime
3640	Lime & Shale
3772	Lime
3942	Lime
3994	Lime
4075	Lime & Chert
4129	Lime
4150	Total Depth

DEC 15 1976  
12-15-76  
WICHITA, KANSAS

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

*K. T. Woodman*  
K. T. Woodman