

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

~~15-185-10992000~~

15-185-22705-00-00

API NUMBER \_\_\_\_\_

LEASE NAME Weber-Knoche

WELL NUMBER 1

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

SEC. 28 TWP. 24 SRGE. 13 (E18A)(H)

COUNTY Stafford

Date Well Completed 10-18-96

Plugging Commenced 3-25-96

Plugging Completed 4-1-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Tom Kat, Ltd.

ADDRESS P.O. Box 1471 Great Bend, Ks. 67530

PHONE#(316) 792-6960 OPERATORS LICENSE NO. 5538

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	315'	none
				5 1/2"	4148'	2018'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl... used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each s... Plugged off bottom with sand to 3930' dumped 5 sacks sand. Shot pipe at 2800', 2600', @ 2400', @ 2200', @2010', came loose, pulled casing. Mix and pumped 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, release plug, 125 sacks cement. Shut in 200# PSI (60/40 POZMIX 6% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Tom Kat, Ltd. Great Bend, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 08 1996  
4-8-96  
SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 96

CONSERVATION DIVISION  
WICHITA, KS My Commission Expires: \_\_\_\_\_

IRENE HERZBERG  
State of Kansas  
My Appt. Exp. Aug. 24, 1997

[Signature]  
Notary Public

Form CP  
Revised 05-

620-938-2945

22705

15.185-10992-000

ROTARY DRILLING LOG

OPERATOR: Artwell Company  
Toland No. 1  
SW 35 NW Sec. 28-24-13W,  
Stafford County, Kansas

CONTRACTOR: Prime Drilling Company  
COMM: 12/3/56  
COMP: 12/19/56

Remarks: Set 8-5/8" at 226' with 200  
socks Posmix, 2% C.C.

Formations:

Soil and Sand	411'
Sand	440'
Shale - Sand streaks	227'
Red Sand	405'
Amalgamite	825'
Shale & Shale	1235'
Shale	1770'
Shale & Lims	1865'
Lims	1990'
Lims & Shale	3374'
Lims	3535'
Lims & Shale	3604'
Lims	4067'
Lims & Shale	4090'
Lims	4166'
Shale & Lims	4178'
Entry Total Depth	4178'

Surface  
Casing

KB.1940

RECEIVED

AUG 06 2002

KCC WICHITA

Long string

Set 5-1/2" production string at 4178'  
cemented with 150 sacks posmix.

We certify the above log is true and  
correct to the best of our knowledge  
and belief.

PRIME DRILLING COMPANY

R.R. McFerial

R. B. McFerial

*P. H.*  
3757-60  
3768-70  
3775-76  
3795-03  
3822-30  
3834-36

Plugged back to 3880