

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

Stafford County, Sec. 28 Twp. 24 Rge. (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines: CEL NE NE

Lease Owner Atlantic Richfield Co.
Lease Name Lyons Well No. 2
Office Address Box 849, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed April 26 1971
Application for plugging approved 19
Plugging commenced April 27 1971
Plugging completed May 10 1971
Reason for abandonment of well or producing formation depleted



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4116 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	461'4"	10"	461'4"	none
		0	4112'	7"	4112'	2048.90

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 4090' and dumped 6 sacks of cement.

Plugged well with 2 sacks of hulls, 20 sacks of gel and 120 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1971

George A. Meyer
Notary Public.

My commission expires Feb. 10, 1975


COPY

ATLANTIC REFG. CO.
 Lyons No. 2.

SEC. 28 T. 24 R. 13W
 CEL NE NE
 660' S NL 330' W EL NE $\frac{1}{4}$

Total Depth. 4116'
 Comm. 7-5-38 Comp. 8-6-38
 Shot or Treated. No
 Contractor. Reading & Bates, Inc.
 Issued. 8-27-38 Rotary w/ cable
 tool completion.

County. Stafford



CASING:
 10" 461'4"
 7" 4112'

Elevation.

Production. Pot. 557 B.

Figures Indicate Bottom of Formations.

surface clay	30	lime & chert	3785
sand	105	lime	3800
shale	120	lime & chert	3810
gravel	200	lime & shale	3835
sand, shells, shale	462	lime, chert & shale	3872
rod rock, shale, shells	655	lime & chert	3890
red rock	760	shale & chert	3918
anhydrite	790	shale	3965
Top Anhydrite 760		chert	3982
red bed & shale	880	chert & shale	4040
shale & shells	950	chert & lime	4062
shale	1030	lime, green shale	4101
shale & shells	1510	core #2 12' recovery 4101-4116	
shale & salt	1620	shale	4114
shale	1640	lime	4116
lime	1650	core #3 2' recovery	4118
shale	1675	6" shaly cherty dolomite	
brkn lime	1710	1 1/2' porous grey dolomite	
brkn limo & shale	1828	w/ spotted saturation	
lime	1845	Correction to derrick floor	
lime & shale	1895	4118 equals 4116	
brkn lime & shale	2065	Total Depth.	
brkn limo	2215		
brkn limo & shale	2375		
brkn lime	2415		
shale & lime	2450		
brkn limo	2640		
lime & shale	2680		
brkn lime & shale	2730		
lime & shale	3125		
lime	3135		
shale	3150		
brkn limo	3190		
lime & shale	3250		
lime	3260		
lime & shale	3280		
lime	3312		
lime & shale	3335		
brkn lime	3395		
brkn lime & shale	3640		
lime	3735		
Core #1 4' recovery 3735-3753			
honeycombed oolitic lime			

RECEIVED
 STATE CORPORATION COMMISSION
 APR 27 1971
 CONSERVATION DIVISION
 Wichita, Kansas