

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

22034-0000
 API NUMBER 15-185-22039

LEASE NAME Paulsen

WELL NUMBER #1-22

1980 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 22 TWP. 24 RGE. 11 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 10-10-87

Plugging Completed 10-20-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Rupe Oil Company, Inc.

ADDRESS Box 2273, Wichita, Kansas 67201

PHONE# (316)-286-5553 OPERATORS LICENSE NO. 5047

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	291'	None
				5-1/2"	3898'	2,992.36'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3770' and 5 sacks cement. Shot casing at 3200' and 3000'. Pulled 73 joints of 5-1/2" casing. Halliburton squeezed well with 3 sacks hulls, 20 sacks gel, 50 sacks 60/40 pozmix cement with 6% added gel and 3% calcium chloride, 5 sacks gel, 1 sack hulls, released plug and pumped 100 sacks cement.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold


(Address) Box 698, Great Bend, Ks. 67530

10-23-86

OCT 23 1986

SUBSCRIBED AND SWORN TO before me this 21st day of October, 1986

My Commission Expires:



Iona M. Leatherman
 Notary Public