

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Knighton Oil Company, Inc.

ADDRESS 221 South Broadway-#710, Wichita, Kansas  
67202

PHONE#( 316 264-7918 OPERATORS LICENSE NO. 5010

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/15/92 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation N/A Depth to Top \_\_\_\_\_ Bottom T.D. 4133

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
 KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

12-8-92

DEC 08 1992

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	332'	8-5/8"	321'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Bottom plug @ 960' w/50 sacks cement through drill pipe (60/40, 9% Gel). Next plug @ 360' w/50 sacks cement through drill pipe (60/40, 9% Gel). Top plug @ 40' w/10 sacks cement through drill pipe (60/40, 9% Gel), 15 sacks in Rat Hole, 10 sacks in Mouse Hole, 5 sacks in water well. (60/40, 9% Gel)  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P. O. Box 823, Great Bend, Kansas 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Earl M. Knighton, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Earl M. Knighton, Jr.

(Address) 221 South Broadway #710  
 Wichita, Kansas 67202



Subscribed and sworn to before me this 7th day of December, 19 92

Sarah A. Simon  
 Notary Public

My Commission Expires: 12/11/93 Sarah A. Simon