

STATE OF KANSAS
STATE CORPORATION COMMISSION
240 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,688-00-00

LEASE NAME Doran

WELL NUMBER 2-14

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 14 TWP. 24 RGE. 15W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 10-18-90

Plugging Completed 10-22-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS P.O. Box 158 Belpre, KS. 67519

PHONE#(316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4160'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	265'	none
				4 1/2"	4155'	2235'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom was already plugged. Shot @2836', 2634', 2431', 2235'.
Plugged with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull,
100 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl Company

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 29 day of Oct, 19 90

My Commission Expires:



Notary Public

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - DORAN #2-14

Located: NW NW NW, Section 14-24S-15W, Stafford County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 21, 1982

COMPLETED: October 28, 1982

TOTAL DEPTH: 4160'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 24# casing. 252.64' pipe set at 265' K.B. Cemented with 210 sacks 60/40 Pozmix with 3% cc. Plug down 4:15 PM, 10-21-82, by Howco.
90 - 268 Shale and Clay	
268 - 959 Shale, Sand, Red Bed	
959 - 974 Anhydrite	
974 - 1110 Shale and Shells	
1110 - 1820 Shale - Lime Stringers	
1820 - 4160 Lime and Shale	Ran 13 joints used 4 1/2", 10.5# casing and 90 joints new 4 1/2", 10.5# casing. 4145.98' pipe set at 4155' K.B. Cemented with 100 sacks Lite and 125 sacks 50/50 Pozmix plug our regular additives. Plug down at 10:45 AM, 10-28-82, by Howco. Plugged rat hole with 10 sacks Lite and water well with 5 sacks Lite.

RECEIVED

Deviation Surveys:

1° at 2101'

1 1/2° at 3805

OCT 4 1990

EXPLORATION DIVISION
Wichita, Kansas