


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County, Sec. 14 Twp. 24 Rge. 15 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Dunne-Gardner Drilling Co., Inc.
Lease Name Burmeister Well No. 1
Office Address 300 Schweiter Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 5, 19 61
Application for plugging filed August 5, 19 61
Application for plugging approved August 5, 19 61
Plugging commenced August 5, 19 61
Plugging completed August 5, 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4343 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	220'	8-5/8"	7-27-61	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with heavy mud to 200 feet from surface. Set plug, 1/4 sack of hulls and 20 sacks of cement. Fill surface pipe with heavy mud to 35 feet from surface. Set plug 1/4 sack of hulls and 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1961
8-8-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Don Gardner (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Gardner
300 Schweiter Building
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 61

My commission expires December 14, 1961

Martha Gogges
Martha Gogges Notary Public.



6
15-185-01197-00-004-24-15W

DRILLER'S LOG

COMPANY: Dunne-Gardner Drilling Co., Inc.
 300 Schweiter Building
 Wichita 2, Kansas

LEASE: Burmeister

WELL: No. 1

LOCATION: NE NE SW Section 14, Township 24 South, Range 15 West,
 Stafford County, Kansas

DATE COMM: July 26, 1961

DATE COMPL: August 5, 1961

T. D.: 4343 Feet

CASING: 8 5/8" casing set @ 200' w/190 sacks cement

<u>FROM</u>	<u>TO</u>	
0	85	Surface shale and sand
85	965	Shale
965	982	Anhydrite
982	1620	Shale
1620	1920	Shale and shells
1920	3080	Lime and shale
3080	3175	Shale
3175	3380	Shale and lime
3380	3490	Lime
3490	3720	Lime and shale
3720	4200	Lime
4200	4270	Lime and chert
4270	4320	Lime
4320	4343	Arbuckle
	4343	T.D.
		D&A

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 7 1961
 CONSERVATION DIVISION
 Wichita, Kansas

I certify the above to be true and correct to the best of my knowledge and belief.

DUNNE-GARDNER DRILLING CO., INC.
 By Don Gardner
 Don Gardner

Subscribed and sworn before me this 14th day of August, 1961.

Martha Gorges
 Martha Gorges - Notary Public

My commission expires:

December 14, 1961