


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

STAFFORD County. Sec. 13 Twp. 24 Rge. 15W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner SANTA-FE PIPE & SUPPLY, INC
Lease Name ENGLISH Well No. 1
Office Address BOX 562, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL
Date well completed JULY 21 19 54
Application for plugging filed JUNE 16 19 66
Application for plugging approved JUNE 17 19 66
Plugging commenced JULY 11 19 66
Plugging completed JULY 18 19 66
Reason for abandonment of well or producing formation DEPLETED
If a producing well is abandoned, date of last production MAY 19 66
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4210 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	220	NONE
				5 1/2"	4208	3597

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4210' - 4075' - SAND
4075' - 4045' - 5 SACKS CEMENT
4045' - 210' - MUD
210' - 200' - ROCK BRIDGE
200' - 185' - 5 SACKS CEMENT
185' - 125' - 20 SACKS CEMENT
125' - 40' - MUD
40' - 30' - ROCK BRIDGE
30' - BASE - 10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1966
7-29-66
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T.L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.L. Nutt
BOX 562, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 28TH day of JULY, 1966

My commission expires JULY 31, 1966
Mary M. Guenier
Notary Public.


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GREENLAND DRILLING CO. et al
Form- English No. 1

SEC. 15 T. 24 R. 15W
NW NW NW

Total Depth. 4210
Comm. 6-17-54 Comp. 7-21-54
Shot or Treated.
Contractor. Greenland Drilling Co.
Issued. 12-24-55

County Stafford
KANSAS



CASING:
8 5/8 220'
5 1/2 @ 4208'

Elevation. 2006 DF

Production. 186 BOPD

Figures indicate Bottom of Formations.

sand & clay	70
shale w/ sand streaks	155
shale & shells	280
red bed w/ sand streaks	956
anhydrite	977
shale & shells	1275
shale & shells w/ salt	1775
lime & shale	1830
lime & shale breaks	2020
lime	2075
lime & shale	2205
lime w/ shale breaks	2340
shale & lime	2935
lime & shale breaks	3025
shaled lime	3110
lime w/ shale breaks	3155
lime & shale	3365
lime, silt & shale	3419
shale & silt w/ lime streaks	3502
lime	3525
Heebner shale	3530
lime & shale	3582
shale & sandy shale	3638
sandy shale	3685
brown lime	3689
shale	3696
Lansing-K. C. lime	3717
lime	3973
lime & shale	4026
conglomerate	4101
chert	4118
conglomerate	4147
Viola	4158
chert	4173
Simpson shale	4184
Simpson shale & sand	4210
Total Depth	

TOPS:	
Heebner	3543
Toronto	3564
Douglas	3581
Brown lime	3685
Lansing	3696
Base K. C.	4006
Penn. Basal conglomerate	4081
Mississippi	4120
Kinderhook	4125
Viola	4133
Simpson	4174

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1966
CONSERVATION DIVISION
Wichita, Kansas