


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 13 Twp. 24 Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines NW/4 NW/4 NE/4
Lease Owner Greenland Drilling Company
Lease Name English "A" Well No. 1
Office Address 506 Union Natl. Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-28 1955
Application for plugging filed 10-28 1955
Application for plugging approved 10-28 1955
Plugging commenced 10-28 1955
Plugging completed 10-28 1955
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4243 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	225	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 215' with 1/3 sack hulls and 20 sacks cement. Filled hole to 35' below cellar and set plug with 30 sacks hulls and 10 sacks cement. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Greenland Drilling Company
Address 506 Union Natl. Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Richard S. Davis (employee of owner) & (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Richard S. Davis, Vice-President
506 Union Natl. Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of October, 1955

Verdina B. Rutledge
Verdina B. Rutledge Notary Public.

My commission expires March 15, 1956.

PLUGGING
FILE SEC 13 Twp 24 R 15 W
BOOK PAGE 18 LINE 20

NOV - 1 1955
11-1-55
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Company: GREENLAND DRILLING COMPANY

Sec. 13-24S-15W
 Loc. NW NW ~~SE~~ NE
 Stafford Co., Kansas

Farm: ENGLISH "A" No. 1

Total Depth: 4244
 Commenced: 10-17-55
 Completed: 10-28-55
 Contractor: GREENLAND DRILLING COMPANY

Casing: 8-5/8" 225' Elevation: 2006 R.B.
 5-1/2" --- Production: D & A

Figures Indicate Bottom of Formations

125	Sand and clay	<u>TOPS:</u>	
225	Shale and shells	Anhydrite	955
275	Shale and shells	Heebner	3569
435	Red Bed with sandy streaks	Brown Lime	3713
465	Sand	Lansing	3724
955	Red bed, shale and shells	Conglomerate	4102
977	Anhydrite	Viola	4164
1510	Shale and shells		
1790	Shale and lime with salt		
1870	Lime and shale		
1955	Shale and lime		
2005	Lime and shale		
2050	Lime		
2335	Lime and shale		
2470	Shale and lime		
2680	Shale and lime streaks		
3215	Shale and lime		
3350	Lime and shale		
3445	Lime and shale with silt		
3522	Shale and lime		
3550	Lime		
3570	Lime and shale		
3574	Shale		
3634	Lime and shale		
3713	Sandy shale		
3718	Brown Lime		
3724	Shale		
3748	Lansing lime		
3973	Lime		
4093	Lime and shale		
4125	Conglomerate		
4171	Shale, lime and chert		
4185	Conglomerate		
4203	Cherty lime		
4234	Viola, chert and lime		
4244	Chert, lime and shale		
4244	T.D.		

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, RICHARD S. DAVIS, of the Greenland Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the #1 English "A" well.

Richard S. Davis
 Richard S. Davis, Vice-President

Subscribed and sworn to before me this 31st day of October, 1955.

Verdina B. Rutledge
 Verdina B. Rutledge, Notary Public

My commission expires March 15, 1956.

PLUGGING
 FILE SEC 13 24 15W
 PAGE 12 LINE 20

NOTARY DIVISION
 Topeka, Kansas