


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. 13 Twp. 24 Rge. 15 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner Greenland Drlg. Co., et al
Lease Name English Well No. 2
Office Address 506 Union Nat'l Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7/15/54 19
Application for plugging filed 7/15/54 19
Application for plugging approved 7/15/54 19
Plugging commenced 7/15/54 19
Plugging completed 7/15/54 19
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4242 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	214'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole @ 210' w/plug & hulls & 20 sks. cement & @ 35'
below cellar w/plug hulls 10 sks. cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Greenland Drlg. Co.
Address Wichita, Ks.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
RICHARD S. DAVIS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19 day of July, 19 54

My commission expires 7/8/57

Mary Ellen Cummins Notary Public.

24-7368-S 3-53-20M

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1954
7-22-54
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE 332 13724 R 15W
BOOK PAGE 49 LINE 2

WELL LOG

Lease Owner: Greenland Drilling Co., ET AL
 Contractor: Greenland Drilling Company
 Farm: English #2
 Total Depth: 4242'
 Comm: 7/21/54
 Comp: 7/15/54
 Casing: 214' of 8 5/8" w/225 cement

Sec. 13-24S-15W
 Loc. SE NW NW
 County: Stafford
 Elevation: 2007 DF
 Production: D & A

Figures Indicate Bottom of Formations:

120 sand & clay
 280 shale & shells
 952 Red Bed w/sd. stks.
 973 Anhy.
 1310 shale & shells
 1620 shale & shells w/salt
 1785 shale & shells
 2035 lime & shale
 2112 lime
 2985 lime & shale
 3145 lime & shale w/silt
 3230 lime w/sh. brks.
 3310 lime & shale
 3440 silt shale & lime
 3525 lime w/sh. brks.
 3548 lime & shale
 3552 Heb. shale
 3618 lime & shale
 3705 shale & sand
 3716 Brn. lime & sd.
 3723 Lans.
 4026 lime
 4098 lime & shale
 4140 Cong.
 4152 Viola
 4169 lime & shale
 4205 lime & shale w/chert
 4242 Viola chert

TOPS:
 Heeb. 3564
 Tronto 3583
 Douglas 3600
 Br. Lime 3705
 Lansing 3717
 Cong. 4100
 Miss. 4129
 Kinderhook 4145
 Maquoketa 4157
 Viola 4167

State of Kansas)
 County of Sedgwick)ss.

I, Richard S. Davis of the Greenland Drilling Company upon oath state that the above and foregoing is a true and correct copy of the log of the English #2 well.

Richard S. Davis
 Richard S. Davis

Subscribed and sworn to before me this 21st day of July, 1954.

Mary Ellen Combs
 Notary Public

My Comm. Exp.: 7/8/57

PLUGGING
 SEC 13-24-15W
 BOX 49-1-1

RECEIVED
 OIL & GAS COMMISSION
 STAFFORD COUNTY