

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 12 Twp. 24 Rge. 15 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. CSL SW SW

Lease Owner Greenland Drilling Company

Lease Name DeVore Well No. 1

Office Address 506 Union Nat'l Bank Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/27/54 19

Application for plugging filed 7/27/54 19

Application for plugging approved 7/27/54 19

Plugging commenced 7/27/54 19

Plugging completed 7/27/54 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4111 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	215	8 5/8	215	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug at 215' w/hulls & 20sks. cement filled hole 35' from bottom of cellar put plug & hulls in w/10sks. cement on top of plug & hulls.

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 - 1954
8-7-54
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Greenland Drilling Company

Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Richard S. Davis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Richard S. Davis*

(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of August, 1954

Mary E. Owen
Notary Public.

My commission expires July 8, 1954

PLUGGING
SEC 12 T24 R15W
PAGE 52 LINE 11

WELL LOG

Lease Owner: Greenland Drilling Co., ET AL Sec. 12-24-15
 Contractor: Greenland Drilling Company Loc. CSI SW SW
 Farm: DeVore #1 County: Stafford
 Total Depth: 4111'
 Comm: 7-16-54 Elevation: 2007 DF
 Comp: 7-27-54 Production: D & A
 Casing: 215' of 8 5/8" 225 sks 3cc


Figures Indicate Bottom of Formations:

100	soil clay & sand	TOPS:	
155	clay & sand	Br. Lime	3661
315	shale & shells	Lans.	3671
942	Red Bed w/sd stks.	Viola	4058
963	Anhy	Simp.	4101
1280	shale & shells		
1780	shale & shells w/salt		
2060	lime & shale		
2105	lime		
2260	lime w/sd & sh brks		
2880	lime & shale		
2950	shale & lime w/silt		
2975	shale & sand		
3315	lime & shale		
3395	lime		
3483	lime shale & silt		
3521	lime & shale		
3526	Hbnr. shale		
3542	lime & shale		
3560	lime		
3587	shale		
3662	sandy shale		
3664	B. lime		
3671	Br lm & sd lm		
3706	Lans lm		
4015	lime		
4055	shale lime & chert		
4072	Cong.		
4101	Viola chert		
4111	Simp shale		

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 7 1954
 CONSERVATION DIVISION
 Topeka, Kansas

State of Kansas)
 County of Sedgewick)ss.

I, Richard S. Davis of the Greenland Drilling Company upon oath state that the above and foregoing is a true and correct copy of the log of the DeVore #1 well.



Richard S. Davis
 Richard S. Davis

Subscribed and sworn to before me this 30th day of July, 1954.

My Comm Exp.: 7-8-57

Mary Ellen Cummins
 Notary Public