

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-19237-0000

API NUMBER

LEASE NAME Suiter

WELL NUMBER #1

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 12 TWP. 24 RGE. 15 (E) or (W)

COUNTY Stafford

Date Well Completed 8-26-65

Plugging Commenced 11-29-88

Plugging Completed 12-13-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hellar Drilling Co., Inc.

ADDRESS 711 Petroleum Bldg. Wichita, Ks. 67202

PHONE# (316) 549-6508 OPERATORS LICENSE NO. 5065

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 13, 1988 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 4112'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	251'	None
				5-1/2"	4092'	2,156.46'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4030' and 5 sacks cement. Shot casing at 3300', 3000', 2700', 2500' & 2150'. Pulled 67 joints of 5-1/2" casing. Howco plugged well with 350# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 150# hulls and 100 sacks 60/40 pozmix cement with 6% gel. Max. pressure was 550 psi & shut in 300 psi.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hellar Drilling, Co. Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1988

My Commission Expires



Notary Public

DRILLER'S LOG

COMPANY: Hellar Drilling Company, Inc.
 CONTRACTOR: Hellar Drilling Company, Inc.
 LEASE: #1 Suiter
 LOCATION: NE SW NW 12-248-15W, Stafford County, Kansas
 COMMENCED: June 17, 1965
 COMPLETED: June 26, 1965
 CASING: Set 8 5/8" surface casing @ 251'/200 sacks cement
 Set 5 1/2" casing @ 4092'/150 sacks cement

0-157	Sand, surface clay, gravel
157-251	Shale
251-950	Shale, Red Beds & sand
950-1505	Shale & Red Beds
1505-1768	Shale, Salt Section
1768-2105	Ft. Riley lime & chert
2105-2332	Lime & shale
2332-2923	Shale & lime
2923-3248	Lime & shale
3248-3390	Lime
3390-3505	Lime & shale
3505-3661	Shale & lime
3661-3733	Lime
3733-3817	K. C. lime
3817-3910	Lime
3910-3949	Marmaton lime & shale
3949-4024	Lime
4024-4085	Lime & shale
4085-4096	Arbuckle dolomite
4096	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION

AUG 23 1968

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)

) ss

COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Suiter, located in NE SW NW 12-248-15W, Stafford County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of July, 1965.

My Commission Expires: