

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1963
4-12-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name Edith Hiebsch Well No. # 2

Location NW NE SE Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4488

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Smith & Smith Casing Pulling

Address: Cushing, Oklahoma License No. 205

Operation Completed: Hour 11:00AM Day 6th Month April Year 1963

The Above well was plugged as follows:

372' of 8 5/8" surface pipe cement circulated with 220 sacks. Plugged
back 4322', cemented with 200 sacks. Top fo cement 3475'. Perferated at
4246'. Sanded to 4230', cemented with 5 sacks. Hole was filled to 200'
with mud, 10' rock bridge cemented with 20 sacks. Hole filled to 40'
with mud, 10' rock bridge, cemented with 10 sacks to base cellar.
3440' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

4/11/63
6884-W