

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,543-00-00
NW/4, Sec. 14, T 24 S, R 15 W/E
1320 feet from N/E section line
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Doran Well # 1-14

Operator: F. G. Holl
Name & 6427 East Kellogg
Address Wichita, KS 67207

County Stafford

Well Total Depth 4256 feet 138.32

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 14 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 4245 Perfs 4038-40 4044-46 PBTD 4078

1st plug pumped 30 sx cement to bottom and stopped plug at 3805

2nd plug squeezed through head with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped additional 125 sx cement

Maximum pressure 500# and shut-in pressure 100#

Signed [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 14 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4245 Perfs at 4038-40 4044-46 PBTD 4078'

1st plug pumped 30 sx cement to bottom and stopped plug at 3805'

2nd plug squeezed through head with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped additional 125 sx cement.

Maximum pressure 500# and shut-in pressure 100#.

Remarks: They recovered 2303' of 4 1/2" production casing. Use 60/40 Pozmix 2% gel

3% cc. by Allied.

RECEIVED
STATE CORPORATION COMMISSION
FEB 29 1984
2-29-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed [Signature]
(TECHNICIAN) ✓

INVOICED
DATE 3-5-84
INV. NO. 0515