

KANSAS

4

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1966
7-22-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name English Well No. # 1

Location NW NW NW Sec. 13 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4210'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 2:00PM Day 18th Month July Year 1966

The Above well was plugged as follows:

220' of 8 5/8" surface pipe, cemented with 225 sacks. 4208' of 5 1/2" long
string, cemented with 100 sacks. Plug back T.D. 4120'. Top perforation 4100'.
Bottom of the hole was sanded to 4075', and cemented with 5 sacks, through the
dump bailer. 3575' of 5 1/2" long string was recovered from the hole. Bridge plug
was pushed in fluid to 210', rock bridge from 210' to 200'. 6 sacks of cement
was mixed in a barrel, and put on plug at 200', through the dump bailer, and
let set over week end. Hole was bailed dry, and 19 sacks of cement was added
to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/22/66
INV. NO. 3616-u