

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 11-30LOCATION SW SW NESEC. 13 TWP. 29 SRGE. 1WDry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease RoyOperator Kewanee Oil Company Address Box 428, Shidler, OklahomaField Wildcat County SedgwickTotal Depth 3355 Feet.Plugging Contractor C. B. Smith Casing Pulling CompanyPlugging Contractor's License No. 205Address Duncan, Oklahoma

(Describe briefly the manner in which the well was plugged)

8-5/8" casing set at 167.74' C.M. and cemented with 200sacks cement by Halliburton. 5-1/2" casing set at 3328.40' C.M.and cemented with 35 sacks cement by Halliburton. Filled hole withcement from 3355 feet to 3328.40' feet. 5-1/2 inch casing filled withheavy mud from 3328.40' to 2435 feet. Shot off and pulled 2441'61 feetof 5-1/2 inch casing. Filled hole with heavy mud from 2435 feet to162 feet. Cement from 162 feet to 117 feet. Heavy mud from 117 feetto 35 feet. Cement from 35 feet to bottom of cellar. Mud and cementpumped by Halliburton.

By Paul D. Dyer
District Conservation Agent

Date February 7, 1954