

15-095-00766-0004

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued April 13, 1967.RECEIVED
KANSAS STATE CORPORATION COMMISSION

MAY 15 1967

CONSERVATION DIVISION
WICHITA, KANSAS

5-15-1967

Operator's Full Name Skelly Oil CompanyComplete Address: P. O. Box 649, McCook, Nebraska 69001Lease Name Cunningham "B" Unit Well No. # 10Location C N/2 NW Sec. 30 Twp. 27 Rge. 10 (E) (W) WCounty Kingman Total Depth 4212'Abandoned Oil Well Gas Well Input Well X SWD Well D & AOther well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 4:00PM Day 11th Month May Year 1967

The Above well was plugged as follows:

346' of 10 3/4" surface pipe, cemented with 215 sacks. 4211' of 4 1/2" long
string, cemented with 300 sacks. 2015' of 7" long string, cemented with
150 sacks. 116' of 5 3/16" liner set at 2166'. Plug back T.D. 3523'. Top
perferation 3426'. Bottom of the hole was sanded to 3400', and cemented
with 10 sacks, through the dump bailer. 1577' of 4 1/2" long string was re-
covered from the hole. 837' of 7" long string was recovered from the hole.

Fluid in the hole was bailed down to 280', bridge plug and rock bridge from
280' to 270', and cemented with 30 sacks. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 15 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 5/15/67INV. NO. 5218-W