

K KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 13, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska 69001

Lease Name Cunningham "B" Unit Well No. # 16

Location SW NW NW Sec. 30 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 3635'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:30AM Day 16th Month May Year 1967

The Above well was plugged as follows:

333' of 12 1/2" surface pipe, cemented with 300 sacks. 3432' of 7" long string,
cemented with 500 sacks. 5 1/2" liner from 3611' to 3334', cemented with 110 sacks
Plug back T.D. 3599'. Top perferation 3437'. Bottom of the hole was sanded to
3028', and cemented with 20 sacks, through the dump bailer. 1570' of 7" long
string was recovered from the hole. Bridge plug was pushed in fluid to 275',
rock bridge from 275' to 265'. 10 sacks of cement was mixed in a barrel, and
put on plug at 265', through the dump bailer, and let set over-night. Next day
hole was bailed dry, and 30 sacks of cement was added to the plug. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 20 sacks
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 5/19/67

INV. NO. 5254-W