

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued April 13, 1967.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 1 1967  
5-1-67  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Cunningham "B" Unit Well No. # 18

Location NW SW NW Sec. 30 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 3444'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:15PM Day 28th Month April Year 1967

The Above well was plugged as follows:

337' of 12½" surface pipe, cemented with 300 sacks. 3403' of 6 5/8" long  
string, cemented with 500 sacks. This is an open hole. Bottom of the hole  
was sanded to 3375', and cemented with 20 sacks, through the dump bailer.  
1605' of 6 5/8" long string was recovered from the hole. Fluid in the hole  
was bailed down to 220', bridge plug and rock bridge from 220' to 210',  
and cemented with 40 sacks. Hole was filled with mud to 40', rock bridge  
from 40' to 30', and cemented with 20 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 5/1/67

INV. NO. 5139-W