

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued March 22, 1967.RECEIVED
STATE CORPORATION COMMISSION
APR 26 1967
CONSERVATION DIVISION
Wichita, Kansas

4-26-1967

Operator's Full Name Skelly Oil CompanyComplete Address: P. O. Box 649, McCook, NebraskaLease Name Miles "C" Well No. # 2Location NW NW SE Sec. 30 Twp. 27 Rge. 10 (E) (W) WCounty Kingman Total Depth 3466'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 12:45 PM Day 25th Month April Year 1967

The Above well was plugged as follows:

303' of 12 $\frac{1}{2}$ " surface pipe, cemented with 300 sacks. 3410' of 7" long
string, cemented with 500 sacks. This is an open hole. Bottom of the hole
was sanded to 3375', and cemented with 7 sacks. 1802' of 7" long string
was recovered from the hole. Fluid in the hole was bailed down to 275',
bridge plug and rock bridge from 275' to 265', and cemented with 40 sacks.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 20 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 4/26/67INV. NO. 5124-W