

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1967

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 13, 1967.

CONSERVATION DIVISION
Wichita, Kansas

5-8-1967

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska, 69001

Lease Name Cunningham "B" Unit Well No. # 59

Location App. C NW Sec. 30 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 3982'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 4:30PM Day 6th Month May Year 1967

The Above well was plugged as follows:

380' of 10 3/4" surface pipe, cemented with 200 sacks. 3963' of 5 1/2" long
string, cemented with 300 sacks. Plug back T.D. 3503'. Top perferation
3400'. Bottom of the hole was sanded to 3360', and cemented with 20 sacks,
through the dump bailer. 1896' of 5 1/2" long string was recovered from the
hole. Hole was filled with mud to 300', rock bridge from 300' to 290',
and cemented with 30 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 5/11/67

INV. NO. 5193-W