

e
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 13, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska 69001

Lease Name Cunningham "B" Unit Well No. # 26

Location App. C S/2 S/2 NW Sec. 30 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 3460'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 1:30PM Day 3rd Month May Year 1967

The Above well was plugged as follows:

255' of 12 1/2" surface pipe, cemented with 300 sacks. 3406' of 7" long
string, cemented with 500 sacks. This is an open hole. Bottom of the hole
was sanded to 3350', and cemented with 20 sacks, through the dump bailer.
2012' of 7" long string was recovered from the hole. Bridge plug was pushed
in fluid to 240', bridge plug and rock bridge from 240' to 230'. 10 sacks of
cement was mixed in a barrel, and put on plug at 230', through the dump bail-
er, and let set over-night. Hole was bailed dry, and 30 sacks of cement was
added to the plug. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 20 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICE RECEIVED
STATE CORPORATION COMMISSION

Signed: Audie Elving
Well Plugging Supervisor

DATE 5/5/67 MAY 5 1967

INV. NO. 5171-W

CONSERVATION DIVISION
Wichita, Kansas

5-5-1967