

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued March 22, 1967.

Operator's Full Name Skelly Oil Company

Complete Address P. O. Box 649, McCook, Nebraska

Lease Name Miles "C" Well No. # 1-A

Location App. C N/2 N/2 SE Sec. 30 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 3500'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:00 P.M. Day 19th Month June Year 1967

The above well was plugged as follows:

236' of 15 1/2" surface pipe, cemented with 250 sacks. 3422' of 6 5/8" long
string, cemented with 550 sacks. This is an open hole. Bottom of the hole was
sanded to 3400', and cemented with 20 sacks, through the dump bailer. 1414'
of 6 5/8" long string was recovered from the hole. Bridge plug was pushed in
fluid to 225', bridge plug and rock bridge from 225' to 215'. Hole was flowin
with water, and was squeezed. 200 sacks of cement was pumped into the surface
pipe, with no pressure, through a 15 1/2" swage. Next day cement was down to 105,
and hole was still seeping water. 150 sacks of cement was pumped to a pressure
of 600 Lbs, through a 15 1/2" swage. Next day cement was down to 18', and hole
was capped with 20 sacks from 18' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

This cementing was done by
Halliburton Cementing Company.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/21/67
INV. NO. 5436-4