

RECEIVED  
STATE CORPORATION COMMISSION  
Form CP-4  
Rev. 12-15-80

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

SEP 28 1982

CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 18 TWP. 24 RGE. 14W E/W  
Location as in quarters or footage from lines:  
NW NW NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner F.G. Holl  
Lease Name Suiter #1 Well No. \_\_\_\_\_  
Office Address 6427 E. Kellogg Wichita, Ks. 67207  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 9-16-82  
Plugging completed 9-24-82  
Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4152'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	215'	none
				4-1/2"	4151'	2033'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 3995' and ran 5 sacks cement. Shot casing @3520', 3278', 3013', 2541', 2211', 2023' and pulled a total of 63 joints of 4-1/2" casing. Plugged well with 4 sacks hulls, 30 sacks gel, 8-5/8" plug and 170 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 19 82

My Commission expires:



Irene Hogver  
Notary Public.