

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County, Sec. 18 Twp. 24S Rge. (E) 11 (W)

Location as "NE/CNW&SW" or footage from lines C-SE-SE-NE

Lease Owner Sunray Mid-Continent Oil Company

Lease Name Holderness Well No. 1

Office Address Box # 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 11, 19 56

Application for plugging filed May 15, 19 56

Application for plugging approved May 16, 19 56

Plugging commenced May 11, 19 56

Plugging completed May 11, 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation Depth to top Bottom Total Depth of Well 4335' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	296'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drlg mud, set Halliburton plug and pushed to 300' with 35 sack cement. Filled hole with drlg mud, set Halliburton plug and pushed to 35' with 10 sacks cement. Cement to surface. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Co.

Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Norman E. Montgomery (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman E. Montgomery
Box # 788, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21 day of May, 1956

My commission expires Dec. 24, 1956

Notary Public.

PLUGGING
FILE SEC. 18 T. 24 R. 14W
BOOK PAGE 61 LINE 29

STATE CORPORATION COMMISSION
MAY 22 1956
CONSERVATION DIVISION
Wichita, Kansas

5-22-56

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
May 18, 1956

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: April 30, 1956
Drilling Completed: May 11, 1956

Holderness #1 - NE/4 of
Section 18-24S-14W, Stafford
County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

Sand & Shale	165
Shale & Shells	405
Sand	465
Shale	943
Anhydrite	963
Shale & Shells	1730
Lime & Shale	2515
Shale & Lime	2690
Lime & Shale	3775
Lime	3990
Conglomerate	4108
Cherty Lime	4157
Sand	4162
Cherty Lime & Shale	4208
Chert & Lime	4236
Cherty Lime	4270
Lime & Shale	4324
Lime	4335 TD

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray Mid-Continent Oil Company, Holderness #1 - NE/4 of Section 18-24S-14W, Stafford County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956
My Commission Expires

RECEIVED 5-22-56
STAFFORD COUNTY, KANSAS

PLUGGING
FILE SEC. 18 T. 24 R. 14W
BOOK PAGE 61 LINE 39