


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 18 Twp. 24 Rge. 14 ~~XXX~~ (W)
Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner J. W. Hershberger
Lease Name Suiter Well No. 1
Office Address Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8 Sept. 19 62
Application for plugging filed 8 Sept. 19 62
Application for plugging approved 8 Sept. 19 62
Plugging commenced 8 Sept. 19 62
Plugging completed 8 Sept. 19 62
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4,153 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug, hulls and 20 sacks cement at 180'. Set plug hulls and 10 sacks cement at 35'. 2 sacks in rat hole

RECEIVED
STATE CORPORATION COMMISSION

DEC 3 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Burt Drilling Co.
Address 1823 Washington, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Duke C. Burt (Employer/Owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Duke C. Burt
1823 Washington, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 30 day of November, 1962

My commission expires August 26, 1965 Jona George Notary Public.



JAMES W. HERSHBERGER
1039 First National Bank Bldg.
Wichita 1, Kansas

Well: Suiter No. 1
Commenced R.D.: 8/29/62
Completed R.D.: 9/ 8/62
Total Depth: 4,153' D.F.
Casing: 203' of 8 5/8' 24# Surface Pipe

Sec. 18-24-14W
Stafford County, Kansas
Elevation:
Initial Prod.: D & A
Contractor: DUKE BURT
DRILLING CO.

Strata	Depth
Sand	0- 100'
Shale	100- 204
Shale & redbed	204- 420
Sand (Dakota)	420- 520
Shale & shells	520- 950
Anhydrite	950- 975
Shale & shells	975-1890
Shale w/lime streaks	1890-2237
Line w/shale streaks	2237-2250
Shale w/lime streaks	2250-2522
Shale & lime	2522-2965
Lime & shale	2965-3258
Line w/shale streaks	3258-3345
Lime & shale	3345-3500
Lime	3500-3620
Shale & lime	3620-3715
Lime	3715-3730
Lime (Lansing)	3730-3750
Lime	3750-4030
Lime & chert	4030-4112
Lime (Mississippian)	4112-4153

RECEIVED
STATE CORPORATION COMMISSION

DEC 3 1962

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by daily reports.

DUKE BURT DRILLING COMPANY

Duke Burt

Signed and sworn to in my presence this 11 day of September, 1962.

Zona George
Notary Public

M. Commission Expires: August 26, 1965