


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County. Sec. 17 Twp. 24S Rge. (E) 14 (W)  
Location as "NE/CNW%SW%" or footage from lines. C N/2 SE SE  
Lease Owner Natural Gas and Oil Company  
Lease Name Denker Well No. 2  
Office Address Box 105, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) lost hole  
Date well completed June 10 19 56  
Application for plugging filed June 27 19 56  
Application for plugging approved June 29 19 56  
Plugging commenced July 2 19 56  
Plugging completed July 3 19 56  
Reason for abandonment of well or producing formation Casing collapsed - unable to complete well.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4310 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		-0-	211	10 3/4"	211	-0-
		-0-	4301	7"	4301	3178

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Oil string cement not drilled out  
Shot pipe at 3170'  
Mudded hole to 200'  
Set 10' rock bridge  
Dumped 20 sacks cement.  
Cement set 12 hrs - hole tested dry  
Mudded hole to 35'  
Set rock bridge  
Ran 10 sacks cement to top of surface pipe

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E and L Casing Pulling Co.  
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
J. B. STEELE, JR. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. B. Steele, Jr.*  
Box 105, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 56  
*Richard R. Brack*  
Notary Public.

My commission expires July 27, 1959

cc: State Corporation Commission  
New Orleans - 2  
Wichita  
File

24-7368-S 3-53-20M

PLUGGING  
FILE SEC 12 T 24 R 14w  
BOOK PAGE 75 LINE 21

RECEIVED  
STATE CORPORATION COMMISSION  
7-10-56

NO. 2 DRINKERWELL RECORD

Location: C N/2 SE SE, 17-24S-14W  
Stafford County, Kansas

Commenced: May 27, 1956

Operator: Natural Gas and Oil Corporation  
Route 1, Great Bend, Kansas

Completed: June 11, 1956

Elevation: 1984 KB

Contractor: Messman-Rinehart Drilling Company  
Petroleum Building, Wichita, Kansas

Production: Oil

Casing Record: 10 3/4" @ 211' w/200 sx cem.  
7" @ 4301' w/150 sacks cem.

.....L O G.....

Clay-Sand	97
Shale	212
Red Bed-Shale	650
Shale	985
Anhydrite	951
Shale	1270
Shale-Lime	1775
Line-Shale	2112
Line (Fort Riley)	2305
Line-Shale	2458
Shale-Lime	2595
Line-Shale	2720
Shale-Lime	2910
Shale	3070
Line-Shale	3150
Shale-Lime	3400
Line-Shale	3609
Line	3694
Line-Shale	3780
Line	3920
Line-Shale	3972
Line-Chert	4055
Cherty Line	4072
Line-Chert	4114
Chert	4120
Viola Chert	4153
Chert-Line	4180
Chert	4215
Viola Line	4240
Line-Sand	4280
Line	4305
Arbuckle	4310 R.T.D.

6-29-58

Sample Tops:

Lansing 3679 (-1695)  
Viola 4098 (-2114)  
Simpson 4240 (-2256)  
Arbuckle 4297 (-2313)

The undersigned, MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

MESSMAN-RINEHART DRILLING COMPANY

By: J. A. Gilliland  
J. A. Gilliland

Subscribed and sworn to before me this  
11th day of June 1956.

Juanita L. Lewis  
Notary Public

My Commission Expires: November 5, 1958

