

15-015-21718-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Butler SEC. 28 TWP. 27 RGE. 6 E/WX
Location as in quarters or footage from lines:
NW-SW-NE

		*	

Locate Well
correctly on above
Section Platt.

Lease Owner Oil Interests Limited
Lease Name Simmons Well No. #1 "D"
Office Address 1115 E. Waterman Wichita, Ks 67211
Character of Well (Completed as Oil, Gas or Dry Hole): dry hole
Date Well Completed 4/25/81
Application for plugging filed Yes
Plugging commenced 4/25/81
Plugging completed 4/25/81

Reason for abandonment of well or producing formation
dry hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dan Thompson, El Dorado, Ks

Producing formation None Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

50 sax of cement were used in plugging this hole. 3 standard well plugs were purchased from Halliburton. The first plug was pushed down to 200' and 30 sax of cement pumped on top. The second is set at 40' and is covered by 15 sax of cement. The final plug is 5' from GL and covered with 5 sax.


RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Durr Drilling and Development

STATE OF Kansas COUNTY OF Sedgwick, ss.
Carl Durr (~~employee of owner~~ operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Durr
Box 788 Claremore, Ok 74017
(Address)



Fred G. Arasmith
Fred G. Arasmith Notary Public.

My Comm. Expires November 5, 1984

DLM DRILLING

27-6

Operator Oil Interest LTD

Type of Well

Well No. #1 "D"

Lease Name *Simmon*

Butler Co.

Elev. 1380 GL

S28 T 27 S 6 E

Well Log

Geological Markers

Formation Description	Top	Bottom	Name	Depth
Shale, Gray				2660
Shale, Tan				2720
Lime, Chirt	2736		Mississippi	2736
Sand	3088		Misner	3088
Sand	3091		Viola	3091
Sand	3106		Simpson	3106
Lime, Dolomite	3140		Arbuckle	3140
TD				3160

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1981
CONSERVATION DIVISION
Wichita, Kansas

Date Received

Signature

Carl Durr

Title

SEC. TRES

Date

6/4/81