

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 015 20253 ⁰⁰⁻⁰⁰

LEASE NAME Smith

WELL NUMBER 2

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 7 TWP. 27 RGE. 8 (E) OF (W) ~~XXXXX~~

COUNTY Butler

Date Well Completed _____

Plugging Commenced 1/7/91

Plugging Completed 1/29/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Flowers Production Co. Inc.

ADDRESS Box 249 El Dorado, Kansas 67042

PHONE# (316) 321 0550 OPERATORS LICENSE NO. 6407

Character of Well SWD ^{FEOR}

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/29/91 (date)

by Don Thompson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3116'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	205	0
				5 1/2	2847	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

SEE PAGE 2 (over)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dale Wilson W W Drilling Co. License No. 6012

Address RR #3 Box 66, El Dorado, Kansas 67042

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dallas Flowers

STATE OF Kansas COUNTY OF Butler, ss.

Dale Wilson (plugging contractor) (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dale Wilson

(Address) RR #3 Box 66, El Dorado, Ks 67042

SUBSCRIBED AND SWORN TO before me this 31st day of January, 19 91

My Commission Expires:

Emma K. Utermoehlen
Notary Public
State of Kansas
My Appt. Exp. 11-12-91

Smith Well #2 SWD plugging report:
Butler County, Kansas Sec 7, Twp 27, Rge 8 E.

1/7/91 Strung up 5" tools. Tools stopped @ 30' from top. Went through bridge. Tools stopped @ 90'. Run impression block . Slivers of tubing./

1/9/91 Clean out with cherry picker to 95'. Bail scale & iron sulfide. Run impression block. no picture.

1/11/91 Put on drilling jars & bit. Drilling on iron @ 97' with bit & cherry picker. Run impression block. Got out sliver of pipe.

1/14/91 Dug cellar. Had swedge cut off of 8 5/8" & 5 1/2" csg, United pumped down 5 1/2" csg. Circulated out 8 5/8" csg. Run 5' of 5 3/4 pipe between 5 1/2 & 8 5/8 Csg.

1/15/91 Pulled 10' of 5 1/2" csg. Had plate welded on 8 5/8" csg. United pumped down 8 5/8" csg. Circulated on outside of 8 5/8" csg.

1/16 Rig down.

1/22/91 rig up.


1/23/91 Run 3 jts of 7 3/8" wash pipe. Washing over 5 1/2" csg from 10' to 92'.

1/24/91 Washing over 5 1/2" csg from 92' to 97'. Pulled wash pipe and had 60' of 5 1/2" csg inside of wash pipe. Run wash pipe & mill.

1/25/91 Milling over 5 1/2" csg from 97' to 107'.

1/28/91 Milling over 5 1/2" csg from 97' to 142'. Pulled wash pipe and mill. Had 20' of 5 1/2" csg and tubing in wash pipe.

1/29/91 Run 7 jts of 3/4" pipe to 142'. United circulated 114 sacks of 60 40 pozmix cement & 2% gel from 142' to surface. Rig down.



Well #2 SWD plugging report:
Cherokee County, Kansas Sec 7, Twp 27, Rge 8 E.

- 7/91 Strung up 5" tools. Tools stopped @ 30' from top. Went through bridge. Tools stopped @ 90'. Run impression block. Slivers of tubing./
- 8/91 Clean out with cherry picker to 95'. Bail scale & iron sulfide. Run impression block. no picture.
- 11/91 Put on drilling jars & bit. Drilling on iron @ 97' with bit & cherry picker. Run impression block. Got out sliver of pipe.
- 14/91 Dug cellar. Had swedge cut off of 8 5/8" & 5 1/2" csg, United pumped down " csg. Circulated out 8 5/8" csg. Run 5' of 5 3/4 pipe between 5 1/2 & 8 5/8 Csg.
- 15/91 Pulled 10' of 5 1/2" csg. Had plate welded on 8 5/8" csg. United pumped down 8 5/8" csg. Circulated on outside of 8 5/8" csg.
- 16 Rig down.
- 22/91 rig up.
- 23/91 Run 3 jts of 7 3/8" wash pipe. Washing over 5 1/2" csg from 10' to 92'.
- 24/91 Washing over 5 1/2" csg from 92' to 97'. Pulled wash pipe and had ' of 5 1/2" csg inside of wash pipe. Run wash pipe & mill.
- 25/91 Milling over 5 1/2" csg from 97' to 107'.
- 28/91 Milling over 5 1/2" csg from 97' to 142'. Pulled wash pipe and mill. d 20' of 5 1/2" csg and tubing in wash pipe.
- 29/91 Run 7 jts of 3/4" pipe to 142'. United circulated 114 sacks of 40 pozmix cement & 2% gel from 142' to surface. Rig down.

FEB 14 1991

CONSERVATION DIVISION
Wichita, Kansas