

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-015-20, 267-0000

LEASE NAME Smith Gray

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

330 Ft. from <sup>N</sup> Section Line

2970 Ft. from E Section Line

SEC. 7 TWP 27 RGE. 8 (E) or (W)

COUNTY BUTLER

LEASE OPERATOR Range Oil Company, Inc

ADDRESS 125 N. Market, Suite 1120, Wichita, KS. 67202

PHONE (316) 265-6231 OPERATORS LICENSE NO. 5120

Date Well Completed 8-11-69

Character of Well SWD-Input FOR

Plugging Commenced 3-13-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-13-00

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Scout card included

Producing Formation Miss Depth to Top 2745 Bottom \_\_\_\_\_ T.D. 2764

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	200'	none
				5 1/2"	2749	1227'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Sand at 2683'. Bailed 5 sacks of Portland. Shot at 1227'. Pulled to 250'. Circulated cement to surface with 123 sacks. Pulled the rest of the pipe. Hole stayed full.

Name of Plugging Contractor Quality Well Service License No. 31925

Address 415 E. Main St., Sterling, Ks. 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Range Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

John M. Washburn (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John M. Washburn


(Address) 125 N. Market, Suite 1120 Wichita, KS 67202

NOTARY PUBLIC - State of Kansas  
PEGGY L. SAILOR  
My Appt. Exp. 2/28/05  
RECEIVED  
STATE CORPORATION COMMISSION

22nd day of March 2000  
Peggy L. Sailor  
Notary Public

My Commission Expires: 12-8-03  
MAR 23 2000

8-122 Map No.  
 OPER DUNNE EQUITIES, INC.  
WICHITA, KS  
 WELL #3 SMITH  
 CONTR WHITE & ELLIS  
 FIELD CONF - TO UNNAMED DISC (MISS)  
 I.P. CO IPP 20 BO + 20 BWP, MISS 2749-64  
API #15-015-20267 *to 215 @ farm @ Kas. (7-95)*



S-T-R 7-275-8E  
 SPOT NE NE NW  
 CO BUTLER, KS  
 ELEV 1561 KB

*Converted to SWD in 10/82?*

SPUD 6-13-69 8 5/8" @ 200 W/140 GEOL - DEAN SEEBER  
 NO CORES  
 DST 1 (MISS) 2747-64, OP 2 HRS, 330' GIP, REC 90' GSY OIL  
 120' HO&GCM, NO ISIP, TAKEN, IFP 23, FFP 92, FSIP  
 800/60 MIN, IFP 1379, FHP 1363  
 RTD 2764, NO LOG 5 1/2" 2749 W/75  
 MICT CO 2764, SO, 1000 ACID, REC LOAD, SWAB 2 1/2  
 BOPH/5 HRS, POP CO IPP 20 BO + 20 BWP, MISS 2749-64  
 COMPLETED 8-11-69

KB SPL TOPS  
 TOR 1424 + 137  
 DG SH 1442 + 119  
 DG SD 1467 + 94  
 BL 1628 - 67  
 LAN 1713 - 152  
 BON SPRGS  
 - KC 1876 - 315  
 - BKC 2025 - 464  
 - LAY SD 2182 - 621  
 - ALT 2190 - 629  
 - PAW 2310 - 749  
 - FS 2346 - 785  
 - FS 2424 - 863  
 - CHER SH 2476 - 915  
 - ARD 2558 - 997  
 - BV SD 2658 - 1097  
 - B/BV 2678 - 1117  
 - MISS CH 2745 - 1184  
 - MISS DOL 2754 - 1193  
 - RTD 2764 - 1203  
 TD IN MISS FORM

COMP ISSUED 8-15-69

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 23 2000

CONSERVATION DIVISION  
 Wichita, Kansas