

KANSAS

Form CP-3  
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 03 1978

CONSERVATION DIVISION  
Wichita, Kansas  
(of this well)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

Operator's Full Name Alpine Drilling Co, Inc.

Complete Address 800 Bitting, Bldg, Wichita, Ks - 67202

Lease Name Freda Ulsch Well No. 1

Location SW-SE-SW- Sec 20 Twp. 24 Rge. 14 (E) (W) X

County Stafford Total Depth 4373

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Felsa Casing Pulling

Address Box 176 Chase, Ks - 67524 License No. 683

Operation Completed: Hour 10 Am Day 30 Month March Year 1978

The above well was plugged as follows:

292'-8 5/8" Casing w/ 225 sap Cement - 5 1/2" Casing set @  
4372' w/ 125 sap Cement - pref. 4112'-22' plug back to  
4075' - Sand back to 4050' - topped w/ 5 sap mixed Cement  
w/ dump bailer. Pull 3017'-5 1/2" Casing - Allied  
Cementing Co. mixed & pumped 3 sap hells - 25 Gel  
release plug - mixed & pump - 125 sap Cement - 27 1/2  
37 cc to top of Casing - "O" Shut-in press -

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 4-4-78

WELL NO. 1050-W