

A
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 28, 1967.

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas 67530

Lease Name Denker Well No. # 2-A

Location C N/2 SE SE Sec. 17 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 4310'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 11:30AM Day 11th Month June Year 1967

The Above well was plugged as follows:

209' of 10 3/4" surface pipe, cemented with 200 sacks. 4304' of 7" long string,
cemented with 125 sacks. Plug back T.D. 3960'. Top perforation 3800'. Bottom of
the hole was sanded to 3750', and cemented with 7 sacks, through the dump bailer
2200' of 7" long string was recovered from the hole. Bridge plug was pushed in
fluid to 200', bridge plug and rock bridge from 200' to 190'. 9 sacks of cement
was mixed in a barrel, and put on plug at 190', through the dump bailer, and let
over-night. Next day hole was bailed dry, and 21 sacks of cement was added to
the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 6/14/67

INV. NO. 5391-4