

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1963

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name D. R. Lauck Oil Co., Inc.Complete Address: 301 S. Broadway, Wichita, KansasLease Name Denker Well No. # 1Location SE NE SE Sec. 17 Twp. 24 Rge. 14 (E) (W) WCounty Stafford Total Depth 4292Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glen & Smith Casing Pulling Co.Address: 204 East Sixth, Ellinwood, Kansas License No. 396Operation Completed: Hour 12:15 PM Day 26th Month Nov. Year 1963

The Above well was plugged as follows:

209' of 8 5/8" surface pipe, cement circulated. 4292' of 5 1/2" long string,
cemented with 125 sacks. Plug back to 3920'. Top perforation 3805'. Hole
was sanded to 3800', bottom cemented with 5 sacks. Fluid level was up in
hole. Plug was pushed to 250', 10' rock bridge. 10 sacks cement was mixed
in barrel and put on plug, through dump bailer, and let set over night.
Next morning hole bailed down, and 20 sacks was added to plug. Hole was
filled with mud to 40', 10' rock bridge, cemented with 10 sacks to base
cellar. 2022' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/3/63INV. NO. 8190-WSigned: Archie Elving
Well Plugging Supervisor