

15-095-19119-0000

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasOperator's Full Name Mack Oil Co.Complete Address: 812 Union Center, Wichita, KansasLease Name Stucky Well No. # 1Location C NE SW Sec. 20 Twp. 27 Rge. 6 (E) (W) WCounty Kingman Total Depth 3950Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     Other well as hereafter indicated:     Plugging Contractor: Knight Casing Pulling Co.Address: Box 304, Chase, Kansas License No. 436Operation Completed: Hour 12:30 PM Day 23rd Month Oct. Year 1963

The Above well was plugged as follows:

285' of 8 5/8" surface pipe, cement circulated. 3950' of 2 1/2" tubing  
run for long string, cemented with 220 sacks. Top perferation 3861'.  
Tubing was shot off at 2525', 40 bbls of drilling mud and 10 sacks  
of cement was pumped in tubing at 2525', to kill gas and cement bottom  
of hole. Upper plug was set at 275', with 10' rock bridge, cemented  
with 25 sacks. Hole was filled with mud to 40', 10' rock bridge, cement-  
ed with 10 sacks to base cellar.

2525' of 2 1/2" tubing was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/28/63INV. NO. 7958-11Signed: Arlene Elving  
Well Plugging Supervisor