

15-095-00468000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 9 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Tomlinson Tomilson & Kathol

Complete Address: 1125 Wichita Plaza, Wichita, Kansas

Lease Name Endicott Well No. # 1

Location NE NW SE Sec. 31 Twp. 27 Rge. 6 (E) (W) W

County Kingman Total Depth 4284

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Tomlinson Tomilson & Kathol

Address: 1125 Wichita Plaza, Wichita, Kansas License No.     

Operation Completed: Hour 7:00AM Day 8th Month June Year 1964

The Above well was plugged as follows:

267' of 8 5/8" surface pipe, cemented with 200 sacks. Hole was filled  
with drilling mud to 250', 1st cementing plug, bridged with hulls, on  
fluid at 250', and cemented with 25 sacks. Hole was filled with drill-  
ing mud to 40', 2nd cementing plug, bridged with hulls, on fluid at 40',  
and cemented with 10 sacks to base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 6/9/64  
INV. NO. 9282-W

Signed: Archie Elving  
Well Plugging Supervisor