

15095-00239-0001

Form CP-3
Rev. 6-26-62

Mo
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1964
05-15-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Capital Producers Inc.

Complete Address: 6210 West Kellogg, Wichita, Kansas

Lease Name Robinson Well No. # 1

Location SE SE SE Sec. 32 Twp. 27 Rge. 6 (E) (W) W

County Kingman Total Depth 4504

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Cherokee Drilling Company

Address: 2005 Tower Bldg., Denver, Colorado License No. 350

Operation Completed: Hour 12:30 PM Day 14th Month May Year 1964

The Above well was plugged as follows:

256' of 8 5/8" surface pipe, cemented with 175 sacks. 4394' of 5 1/2" long
string, cemented with 180 sacks. Plug back to 4302'. Top perferation
4252'. Bottom of the hole was sanded to 4240', and cemented with 5 sacks.
Hole was filled with mud to 260', and 10' of rock bridge, cemented with
25 sacks. Hole was filled with mud to 40', and 10' of rock bridge, cem-
ented with 10 sacks to base of the cellar.
3674' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/18/64

INV. NO. 9143-U