

~~MO~~ KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1964
9-25-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Wilkinson Drilling Inc.

Complete Address: 805 Union Center, Wichita, Kansas

Lease Name Nagel Well No. # 1

Location SE SE NE Sec. 10 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4097

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 3:00PM Day 24th Month Sept. Year 1964

The Above well was plugged as follows:

252' of 8 5/8" surface pipe, cement circulated. 3895' of 4 1/2" long
string, cemented with 150 sacks. Plug back to 3799'. Top perforation
3784'. Bottom of the hole was sanded to 3770', and cemented with 3
sacks. A squeeze job was necessary. 10 sacks of Gel-Mud and 75 sacks
of cement was pumped in surface pipe, through an 8 5/8" swage, to a
pressure of 400 lbs. A wiping plug was not run between the Gel-Mud
and the cement, due to a bridge of rock at 40', in the fluid of the
surface pipe. 2500' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/28/64
INV. NO. 9868-W

Signed: Archie Elving
Well Plugging Supervisor