

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1965
11-24-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name High Plains Production Company
Complete Address: 300 Insurance Bldg., Wichita, Kansas
Lease Name Walker Well No. # 1
Location NE NE SE Sec. 10 Twp. 24 Rge. 15 (E) W
County Stafford Total Depth 4160'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling Company
Address: Box 405, Chase, Kansas License No. 436
Operation Completed: Hour 4:00 PM Day 21st Month Nov. Year 1965

The Above well was plugged as follows:

202' of 8 5/8" surface pipe, cemented with 185 sacks. 3883' of 4 1/2" long
string, cemented with 100 sacks. Plug back to 3710'. Top perferation 3689'.
Bottom of the hole was sanded to 3675', and cemented with 4 sacks. 2121' of
4 1/2" long string was recovered from the hole. 10 sacks of Gel-Mud was pumped
into 4 1/2" long string at 400', 25 sacks of cement was pumped into 4 1/2" long
string at 200'. Mud in the hole was at 40', rock bridge from 40' to 30',
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11-29-65
INV. NO. 2261-W

Signed: Archie Elving
Well Plugging Supervisor