

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

OCT 25 1965
10-25-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Fender Pipe & Supply, Inc.

Complete Address: Box 302, Russell, Kansas

Lease Name Petro Well No. # 1

Location SW SW NE Sec. 9 Twp. 24 Rge. 15 (E) W

County Stafford Total Depth 4100'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:15AM Day 22nd Month Oct. Year 1965

The Above well was plugged as follows:

236' of 8 5/8" surface pipe, cement circulated. 4097' of 5 1/2" long string,
cemented with 200 sacks. Plug back to 3750'. Top perforation 3719'. Bottom
of the hole was sanded to 3700', and cemented with 5 sacks. 2990' of 5 1/2"
long string was recovered from the hole. Fluid was up in the hole. Bridge
plug was pushed in fluid to 225'. rock bridged from 225' to 215'. 1 sack of
Cal-Seal and 3 sacks of cement was mixed in barrel, and put on plug at 215',
through the dump bailer, and let set over-night. Next morning hole was bailed
dry, and 21 sacks of cement was added to the plug. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base
of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/26/65
INV. NO. 2051-W