

15-185-10486-0000

Form CP-3  
Rev. 6-26-62

14 KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1965  
11-1-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Fender Pipe & Supply, Inc.

Complete Address: Box 302, Russell, Kansas

Lease Name Petro Well No. # 2

Location SW NE NE Sec. 9 Twp. 24 Rge. 15 (E) (W)

County Stafford Total Depth 4105'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:15PM Day 31st Month Oct. Year 1965

The Above well was plugged as follows:

226' of 8 5/8" surface pipe, cement circulated. 4105' of 4 1/2" long string,  
cemented with 100 sacks. Top perferation 4046'. All perferation were squeezed  
with 50 sacks. 3266' of 4 1/2" long string was recovered from the hole. Fluid  
was up in the hole. Bridge plug was pushed in fluid to 220', rock bridge from  
220 to 210'. 5 sacks of cement was mixed in barrel, and put on plug at 210',  
through the dump bailer, And let set over-night. Next morning hole was bailed  
dry, and 20 sacks of cement was added to the plug. Hole was filled with mud to  
40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED  
DATE 11/1/65  
INV. NO. 2049-W