

To: 1 052144 6-19  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-185-23,018-0000  
SW NE SW NW, SEC. 13, T 24 S, R 14 W/X  
3538 feet from S section line  
4486 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9324  
Operator: JFW Inc.  
Name & Address 1014 N. Huntsville Rd.  
Plevna, KS 67568

Lease Name Asher B Well # 2-B  
County Stafford 138.13  
Well Total Depth 4250 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Quality Well Service, Inc. License Number 31925  
Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 3 p.m. Day: 19 Month: 6 Year: 19 97

Plugging proposal received from Richard McIntyre  
(company name) Quality Well Service, Inc. (phone) 316-727-3410

Work: 5 1/2" at 4235' w/135 sx cement, Perfs at 3664-68, 3618-23'  
1st plug sand back to 3550' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, release 8 5/8" wiper plug and pump 125 sx cement.

7-27-97  
RECEIVED  
KANSAS CORP COM  
MAY 15 1997

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 19 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 5 sx cement on top of sand  
through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2040' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
DATE JUL 03 1997  
INV. NO. 48479  
6-19

Signed Richard W. Lacey  
(TECHNICIAN)