

1052398

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-20,889-0000  
NE NW SE SEC. 19, T 24 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DEBUSK WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD

141.67

OPERATOR LICENSE # 6016 WELL TOTAL DEPTH 4359 FEET

OPERATOR: CONDOR ENERGY INC. 6/15 PRODUCTION CSG: SIZE 5 1/2" @ 4355' WITH     SX

NAME AND PO BOX 108 SURFACE CASING: SIZE 8 5/8" @ 284' WITH     SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL     INPUT WELL     INJ WELL     D/A    

OTHER WELL AS HEREINAFTER INDICATED    

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 15 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO **RECEIVED** STATE CORPORATION COMMISSION

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945 **JUN 19 2000**

WERE: OPEN HOLE AT 4355-59 CONSERVATION DIVISION  
Wichita, Kansas

1ST PLUG SANDED TO 4300' AND 5 SX CEMENT. SPOTTED PLUGS THROUGH CASING WHILE PULLING.

2ND PLUG AT 922' WITH 10 SX GEL & 50 SX CEMENT. 3RD PLUG AT 315' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART     NONE    

OPERATIONS COMPLETED: HOUR: 4:25 PM DAY: 15 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT    

1ST PLUG SANDED TO 4300' AND 5 SX CEMENT. SPOTTED PLUGS THROUGH CASING WHILE PULLING.

2ND PLUG AT 922' WITH 10 SX GEL & 50 SX CEMENT. 3RD PLUG AT 315' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2300' OF 5 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

**INVOICED**

SIGNED Richard W. Lacey  
(TECHNICIAN)

5A

FORM CP-2/3

DATE 6/21/00

INV. NO. 61883

