

1052402

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-20,911-0000
NE SE SW SEC. 19, T 24 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME (DeBUSH) DEBUSK WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 143.81

OPERATOR LICENSE # 6016 6/16 WELL TOTAL DEPTH 4425 FEET

OPERATOR: CONDOR ENERGY, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4422' WITH SX

NAME AND PO BOX 108 SURFACE CASING: SIZE 8 5/8" @ 334' WITH SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 16 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4422-4425

SAND TO 4380' AND 5 SX CEMENT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 900' WITH 10 SX GEL & 50 SX CEMENT. 2ND PLUG AT 360' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:14 PM DAY: 16 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

SAND TO 4380' AND 5 SX CEMENT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 900' WITH 10 SX GEL & 50 SX CEMENT. 2ND PLUG AT 360' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED STATE CORPORATION COMMISSION

JUN 22 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2100' OF 5 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 6/27/00 SIGNED Richard M. Lacey

(TECHNICIAN)

FORM CP-2/3

CONSERVATION DIVISION WICHITA, KANSAS

INV. NO. 61902

RML