

1052401

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-20,962-0000  
NE SE SW SEC. 19, T 24 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DEBUSK WELL # 5

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 143.33

OPERATOR LICENSE # 6016 6/16 WELL TOTAL DEPTH 4410 FEET

OPERATOR: CONDOR ENERGY, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4410' WITH SX

NAME AND PO BOX 108 SURFACE CASING: SIZE 8 5/8" @ 323' WITH SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL        INPUT WELL        INJ WELL        D/A       

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 16 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4400

SAND TO 4350' AND 5 SX CEMENT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 900' WITH 10 SX GEL & 50 SX CEMENT. 2ND PLUG AT 360' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL        X        PART        NONE       

OPERATIONS COMPLETED: HOUR: 4:15 PM DAY: 16 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT       

SAND TO 4350' AND 5 SX CEMENT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 900' WITH 10 SX GEL & 50 SX CEMENT. 2ND PLUG AT 360' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM) CONSERVATION DIVISION  
Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING.

DATE 6/27/00 SIGNED Richard W. Lacey

(TECHNICIAN)

FORM CP-2/3

INV. NO. 61902