

1082400

TO:
STATE CORPORATION COMMISSIONAPI NUMBER 15-185-20,940-0001
NW NW SE SEC. 19, T 24 S, R 14 WCONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DEBUSK WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORDOPERATOR LICENSE # 6016WELL TOTAL DEPTH 4413 FEETOPERATOR: CONDOR ENERGY, INC.PRODUCTION CSG: SIZE 5½" @ 4413' WITH 150 SXNAME AND PO BOX 108SURFACE CASING: SIZE 8½" @ 343' WITH 235 SXADDRESS GREAT BEND, KS 67530CONDUCTOR CSG: SIZE " @ 'ABANDONED OIL WELL GAS WELL INPUT WELL E-26,597 SWD WELL D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529ADDRESS PO BOX 467, CHASE, KS 67524-0209COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 14 MONTH: 06 YEAR: 2000PLUGGING PROPOSAL RECEIVED FROM MIKE KELSORECEIVED
STATE CORPORATION COMMISSION(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

JUN 19 2000

WERE: PERFS AT 3858-62, 4378-82, 4121-35CONSERVATION DIVISION
Wichita, Kansas1ST PLUG SAND TO 3700' AND 5 SX CEMENT. SPOTTED PLUGS THROUGH CASING WHILE PULLING.2ND PLUG AT 900' WITH 10 SX GEL & 50 SX CEMENT. 3RD PLUG AT 370' WITH 50 SX CEMENT.4TH PLUG AT 40' WITH 15 SX CEMENT.PLUGGING PROPOSAL RECEIVED BY RICHARD LACEYPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE OPERATIONS COMPLETED: HOUR: 2:25 PM DAY: 14 MONTH: 06 YEAR: 2000ACTUAL PLUGGING REPORT 1ST PLUG SAND TO 3700' AND 5 SX CEMENT. SPOTTED PLUGS THROUGH CASING WHILE PULLING.2ND PLUG AT 900' WITH 10 SX GEL AND 50 SX CEMENT. 3RD PLUG AT 370' WITH 50 SX CEMENT.4TH PLUG AT 40' WITH 15 SX CEMENT.REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000 OF 5½" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE

6/21/00

SIGNED

Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3

INV. NO.

61883