

1 080606

15-185-21823-0000

APR 24 1987

API NUMBER 15- N/A

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NE SEC. 20, T 24 S, R 14 W/E

4850 feet from S section line

330 feet from E section line

Lease Name Torluemke Well # 4

County Stafford 142.03

Well Total Depth 4370 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 910

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Operator: Davis Petroleum, Inc.

Name & Address Rt. 1, Box 183-B

Great Bend, KS 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 24 Month: 4 Year: 1987

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4369' Perfs at 4271-4277', 4262-66' Cast Iron Bridge Plug at 4125'
Top Perfs at 4108-4114', 4095-97'

1st plug sand to 4050' and dump 5 sx cement on top of sand through bailer,

2nd plug allow 1st plug to set - sand to 3825' and spot 5 sx cement on top of sand with

bailer, 3rd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and

100 sx cement. Plugging Proposal Received by Don Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 24 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sand back to 3825' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Maximum pressure 850 psi and shut in 700 psi.

4-30-87

Remarks: Recovered 3000' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

DATE 5-4-87

Signed J. H. [Signature] (TECHNICIAN) APR 30 1987

INV. NO. 16700

CONSERVATION DIVISION Wichita, Kansas CP-2/3 Rev. 01-84