

1 040426

6-7

API NUMBER 15- 185-20,983-0000

NW NW NW, SEC. 20, T 24 S, R 14 W/E

4950 feet from S section line

4950 feet from E section line

Lease Name Ulsh Well # 1

County Stafford 141.70

Well Total Depth 4360 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 362

Input Well SWD Well D&A

Operator License # 4419

Operator: Bear Petroleum

Name &

Address Box 438

Haysville, KS 67060

Abandoned Oil Well Gas Well X

Other well as hereinafter indicated

Plugging Contractor Lyons Well Service License Number 30375

Address 1103 S. St. John, Lyons, KS 67554

Company to plug at: Hour: 9:30 a.m. Day: 7 Month: 6 Year: 19 90

Plugging proposal received from Dewey Gressel

(company name) Lyons Well Service (phone) 316-257-5524

were: 4 1/2" at 4359' PBSD 4328' Perfs at 4296-4302'

1st plug set CIBP at 4246' and dump 2 sx cement on top,

2nd plug at 875' with 50 sx cement,

3rd plug at 390' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 7 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4010' and dumped 2 sx of cement on top

of CIBP with bailer,

Spot plugs through 4 1/2" casing: 2nd plug at 875' with 50 sx cement,

3rd plug at 390' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1734' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 6-12-90 JUN 11 1990

INV. NO. 28411 6-7

Wichita, Kansas

Signed Stephen J. Pfeifer (TECHNICIAN)