

To: 1 121068. 9-20
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 185-21,609-0000
NW NE NE, SEC. 20, T 24 S, R 14 W/E
4950 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656
Operator: Davis Petroleum, Inc.
Name & Address RR 1, Box 183 B
Great Bend, KS 67530

Lease Name Torluemke Well # 1
County Stafford 140.63
Well Total Depth 4327 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 11:45 a.m. Day: 20 Month: 9 Year: 19 95

Plugging proposal received from L.D. Davis
(company name) Davis Petroleum, Inc. (phone) 316-793-3051

Work: 4 1/2" at 4325' w/200 sx cement, PBD 4105', Perfs at 4086-92, 4092-98'
1st plug sand back to 4036' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1995

Plugging Proposal Received by _____
CONSERVATION DIVISION
WICHITA (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:15 p.m. Day: 20 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4036' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10
sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Due to broken pressure gauge, unable to check pressure.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2213' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

~~INVOICED~~ observe this plugging.

Signed Dennis Raskin
(TECHNICIAN)

DATE OCT 04 1995
INV. NO. 43648