

1 080605

APR 24 1987 15-185-11987-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-N/A

SE NW NE, SEC. 20, T 24 S, R 14 W/E
4290 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Lease Name Torluemke Well # 3

Operator: Davis Petroleum, Inc.
Name & Address: Rt. 1, Box 183-B
Great Bend, KS 67530

County Stafford 142.55

Well Total Depth 4386 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 24 Month: 4 Year: 1987

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4385' Perfs at 4234-42'

1st plug sand back to 4180' and dump 5 sx cement on top of sand through dump bailer,

2nd plug pump 3' sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Don Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 24 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sand back to 4180' and dump 5 sx cement on top of sand with bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

4-30-87

Remarks: Recovered 3000' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

(could not observe this plugging.)

DATE 5-4-87

Signed J. D. Ubel (TECHNICIAN) APR 30 1987

INV. NO. 16701