

To: 1 121069 9-20
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 185-21,761-∞-∞
NE NW NE, SEC. 20, T 24 S, R 14 W/E
4950 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4656
Operator: Davis Petroleum, Inc.
Name:
Address: RR 1, Box 183 B
Great Bend, KS 67530

Lease Name Torlumeke Well # 2
County Stafford 140.73
Well Total Depth 4330 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 356

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901
Address: P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1:15 p.m. Day: 20 Month: 9 Year: 1995

Plugging proposal received from L.D. Davis
(company name) Davis Petroleum, Inc. (phone) 316-793-3051

were: 5 1/2" at 4329' w/225 sx cement, Perfs at 4089-90'
1st plug sand back to 4000' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 p.m. Day: 20 Month: 9 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 125 sx cement.

Due to broken pressure gauge, unable to check pressure.

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1995

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2139' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE OCT 04 1995

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 43647